



KANSAS GEOLOGICAL SOCIETY.
508 East Murdock
Wichita, Kansas

Shields


12-13-17W
SE NE SE
Russell, Kansas

JUN 20 1970

WELL LOG

Operator: Shields Oil Producers, Inc.
Well: Kuhn #1
Commenced: May 5, 1970
Completed: May 12, 1970
Contractor: Shields Drilling Co., Inc.

Well Description: SE NE SE
Sec. 12-13S-17W
Ellis County, Kansas



CASING RECORD

Size	Run	Pulled
8 5/8"	247'	Cmtd. w/ 150 sax

Elevation: 2,017' RB
Treatment:
Production: D & A *Log*
Tops: Heebner 3,229'
Toronto 3,250'
Lansing-KC 3,280'
Conglomerate 3,522'

..... Figures Indicate Bottom of Formations

Shale	160'
Shale & sand	520'
Shale, sand & redbed	1,166'
Anhydrite	1,204'
Shale & shells	1,400'
Salt, shale & lime	1,690'
Shale & lime	3,000'
Lime	3,580' RTD



NOTES

DST #1 3,282' - 3,315' Tool open w/ weak blow dying in 5 min.
Recovered 10' mud. IBHP-466#, IFP-38#,
FFP-53#, FBHP-not taken.

DST #2 3,330' - 3,363' Tool open w/ weak blow dying in 14 min.
Recovered 15' mud w/ few oil specks.
IBHP-329#, IFP-45#, FFP-65#,
FBHP-109#/30 min.