


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
502 East Murdock, Wichita, Kansas

Company- J. A. DAVIS, J. H. CHILD ET AL
Farm- Karlin No. 3

SEC. 14 T. 13 R. 17W
SE SW NE

Total Depth. 3598 P.B. 3345
Comm. 9-2-51 Comp. 10-14-51
Shot or Treated.
Contractor. Sterling Drlg.
Issued. 3-29-52

County Ellis
KANSAS



CASING:

8 5/8" 160' cem. w/125 sx.
5 1/2" 3542' cem. w/125 sx.

Elevation. 2012 D.F.

Production. Pmp. 40 bbls. /
60 wtr.

Figures Indicate Bottom of Formations.

shale & shells	1180
anhyd.	1220
shale & shells	1825
lime & shale	1940
lime	2320
lime & shale	2915
shale	2980
lime	3511
shale	3517
lime	3541
lime	3558
lime & shale	3582 1/2
Arb.	3598
Total Depth P.B.	3345

Tops: Scout	
Heebner	3231
Lansing	3277
Arb.	3538

Cable Tool Record:

T.D. 3598 no show. Perf. 3437-47 Az.
3500 gal. prod. 1 bbl. oil per hr. P.B.
3400. Perf. 3353-58 az. w/1000 gal. no show
P.B. 3345. Perf. 3306-10; prod. 40 bbls.
oil, 150 bbl. wtr. in 24 hrs. Squeezed
perf. 3325-29; 500 gal. az. 10 bbls. wtr.
per hr. Squeezed perf. 3302 1/2-6 1/2; az. w/500
gal. Prod. 40 bbls. oil & 60 bbls. wtr.
per day. Put on pump.