


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- OVERLAND DRILLING COMPANY  
Farm- Dorzweiler No. 1

SEC. 15 T. 13 R. 17W  
SW NE NE

Total Depth. 3585  
Comm. 12-26-52 Comp. 1-12-53  
Shot or Treated.  
Contractor.  
Issued. 4-11-53

County Ellis  
KANSAS



CASING:  
8 5/8" 163' cem. circs

Elevation. 2003  
*2005 (and)*

Production. Dry

Figures indicate Bottom of Formations.

surface clay	40
sand blue, shale	163
shale & shells	700
sand	825
shale, sand, red bed	1095
red bed, shells	1190
lime, anhydrite	1225
red bed, shells	1415
shells	1724
salt, shale, shells	1860
shale & lime shells	2175
lime	2445
lime & shale	3118
lime	3216
lime & shale	3222
lime	3479
lime	3585

Total Depth

Scout Tops:

Hebner	3226
Lansing	3271
Base-Kansas City	3504
Conglomerate	3532
Arbuckle	3566

DST: 3326' 48' anchor  
BHP 500# rec. 94'  
salt water

Plugging Record:

hole bridged and cement  
plug at 155'-15 sx cement  
10 sx cement plug at 40'.