

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING COMPANY
Farm- Rome "A" No. 11

SEC. 23 T. 13 R. 17W
SE SW SW

Total Depth. 3615'

Comm. 1-26-59

Comp. 2-4-59


Shot or Treated.

Contractor. Murfin Drlg.

Issued. 8-15-59

County Ellis

KANSAS



Elevation. 1967' KE

Production. 66 BOPD

CASING:

8 5/8" 167' cem w/155 sx.
5 1/2" 3613' cem w/75 sx.

Figures Indicate Bottom of Formations.

surface hole	167
shale & shells	350
shale-sand-shells	560
shale & shells	640
sand	820
red bed & shale	1178
Anhydrite-lime	1216
red rock-shale-shells	1555
shale & shells	1720
salt-shale	1835
shale-lime shells	2035
lime-shale	3325
lime	3405
lime-shale	3530
Arbuckle	3615
Total Depth	

TOPS:

Anhydrite (scout)	1178
Topeka	2948
Heebner	3212
Toronto	3232
Lansing-Kansas City	3260
Base Kansas City	3456
Arbuckle	3529

DST #1 3320-56', op 2 hrs., rec. 710' gas
& 130' muddy oil. IF 0#, FF 0#, BHP 155#/20 mins.

DST #2 3532-40', op 1 hr, rec. 15' oil cut
mud & 15' mud. IF 0#, FF 0#, BHP 145#/20 mins.

DST #3 3540-55', op 1 hr., rec. 55' heavily
oil cut mud. IF & FF 0#, BHP 155#/20 min.

DST #4 3561-86', op 1 hr., rec. 12' mud,
IF 0#, FF 0#, BHP 435#/20 min.