

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

THE EL DORADO REFINING CO., &
 Company. ANSCHUTZ DRILLING CO.
 Farm-Braun "B" No. 1

SEC. 26 T. 13 R. 17W
 NW NW SW

Total Depth. 3515

Comm. 12-27-52

Comp. 2-2-53


Shot or Treated.

Contractor. Anschutz Drilling Co.

Issued. 2-28-53

County Ellis

KANSAS



Elevation. 1983 DF

Production. 518 BOPD., -N. W..

Figures indicate Bottom of Formations.

sand & surface clay	45
clay & shale	670
sand	770
red bed & shale	1015
red bed	1165
anhydrite	1225
shale & red bed	1470
shale & shells	2150
lime	2205
lime & shale	3305
lime	3396
lime & shale	3456
lime	3510
D. D.	3515
Total Depth	

TOPS:

Anhydrite	1165
Heebner	3217
Toronto	3237
Lansing	3264
Arbuckle	3507

G.S.O. fair-good inter-xylm por. in

fair-med. xylm dol. 3507-10.

C.O. to RTD 600' OIH/3 hrs. D.D. 3512;

1000' OIH/ 2 hrs. $\$ 9\frac{1}{2}$ BOPH/5 hrs.

600' O.B.

D.D. 3515 T.D. 1900 OIH/2 hrs. $\$ 10$ BOPH/5 hrs.

1200' O.B.

Pmp. 63 BO/3 hrs.