


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- **OIL PROPERTY MANAGEMENT, INC.**
 Farm- **Dreiling "B"** No. **6**

SEC. **27** T. **13** R. **17W**
 SW SE SE

Total Depth. **3525'**
 Comm. **9-19-63** Comp. **9-27-63**
 Shot or Treated.
 Contractor. **H-30, Inc.**
 Issued. **5-15-65**

County **Hillis KANSAS**



CASING:

Elevation. **1979'** D.F.

8 5/8" 176' w/130 sx cem.
4 1/2" 3518' w/100 sx cem.

Production. Pmp. 15 BOPD-NW

Figures indicate Bottom of Formations.

shale, shells	160
shale	176
shale w/sand strks	360
shale, shells	650
sand	870
red bed, shale, shells	1170
Anhydrite	1212
shale, shells	1600
shale, lime	1850
lime, shale	2170
shale, lime	2460
lime, shale	3303
lime	3483
lime, shale	3525
Rotary Total Depth	

TOPS: SAMPLE

Anhydrite	1170
B/Anhydrite	1212
Topeka	2982
Toronto	3245
Lansing	3271
B/Kansas City	3475
Conglomerate	3490
Arbuckle	3516

TOPS: SCOUT

Heebner	3222
Brown lime	3226