


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING CO.
Farm- Von Lintel No. 2

SEC. 26 T. 13 R. 177
NW NE NW

Total Depth. 3655'
Comm. 8-10-59 Comp. 8-21-59
Shot or Treated.
Contractor.
Issued. 1-2-60

County Ellis KANSAS



Elevation. 1270' ±

Production. 10 BOPD

CASING:

8 5/8" 167' cemented /200 sx.
5 1/2" 3655'

Figures indicate Bottom of Formations.

shale & shells	350
shale, sand, shells	355
sand	815
red bed, shale & shells	1164
Anh.	1202
shale & shells	1560
salt & shells	1830
shale, lime, shells	1840
shale, lime	3285
lime	3346
lime, shale	3500
lime Arb.	3520
Arb.	3650
Arb.	3655
Total Depth	

TOPS:

Topeka	2948
Heebner	3208
Toronto	3228
Lansing	3255
Arbuckle	3498

DST #1. 3340-51. Open 30 min. Rec.
5' DM. BHP-0% /30 min.

DST #2. 3272-3351. Open 1 hour,
weak to strong blow throughout
test. Recovered 30' slightly
oil and gas cut mud. IFP 75 #,
FFP 95%, BHP 70%.

DST #3. 3500-3525. Open one hour,
very weak blow for 7 minutes,
dead for 20 minutes, intermittent
20 minutes, recovered 16' oil cut
mud. 30 minutes ISIP 090%,
IFO, FFP 0, FSIP 130%.

DST #4. 3520-3550. Open one hour
weak to fair blow 25 minutes,
fair steady blow throughout test.
Recovered 38' oil and gas cut
mud. 30 minutes. ISIP 1035%,
IFP 0, FFP-0, FSIP 585%.