

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company-D. R. LAUCK OIL CO., INC -H. H. BLAIR SEC. 27 T. 13 R. 17W
 Farm-Geist No. 2 SE SW NE

Total Depth. 3519
 Comm. 10-12-53

Comp. 10-26-53

County Ellis

KANSAS

Shot or Treated.

Contractor.

Issued. 12-19-53

CASING:

8 5/8 205' w/ 135 sx cmt.
 5 1/2 3512.5' w/ 150 sx cmt.

Elevation. 1988 DF

Production. 351 BO

Figures indicate Bottom of Formations.

sand & clay	80
shale	185
shale & shells	640
sand	815
shale & red bed	1195
anhydrite	1230
shale & red bed	1500
shale & shells	2010
lime & shale	2195
broken lime	2285
lime	2295
lime & shale	2920
shale & shells	2980
lime & shale	3063
lime	3519
Total Depth	

TOPS:

Heebner	3224
Lansing	3269
Arbuckle	3510

DST #1: 3294-3320; open 1 hr. rec.
 720' gas, 60' OCM, 240' VHCCM, 360'
 gassy oil, BHP 1000#, 15 min. IFP 30#
 FFP 310#