

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- D. R. LAUCK OIL CO., INC.
Farm- Geist No. 3

SEC. 27 T. 13 R. 17W
C N $\frac{1}{2}$ SW NE

Total Depth. 3530'

Comm. 3-15-54


Comp. 3-29-54

Shot or Treated.

Contractor.

Issued. 5-22-54

County Ellis KANSAS



CASING:
8 5/8" 160' cem w/100 sx
5 1/2" 3530' cem w/125 sx

Elevation. 1994' DE

Production. 283 BO & no wtr.

Figures Indicate Bottom of Formations.

surface clay	40
shale & shells	160
shale, shells & red bed	675
sand & sand stone	910
red bed & shells	1200
anhydrite	1245
shale & lime	2250
broken lime	2320
lime	2370
shale & lime	2995
lime	3527
Arbuckle	3530 RTD
Total Depth	

Tops:

Topeka	2996
Heebner	3241
Toronto	3262
Lansing	3287
Arbuckle	3527

DRILL STEM TESTS:

#1 3289-3322 Open 1 hr., fair steady blow
throughout, rec. 310' slightly oil-cut
and gas-cut muddy salt water; IFP 0
FFP 160# BHP 980# in 20 min.