

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- D. R. LAUCK OIL CO., INC.
 Farm- Geist No. 6


SEC. 27 T. 13 R. 17W
 SW SW NE

Total Depth 3510
 Comm. 4-24-54
 Shot or Treated.
 Contractor.
 Issued. 2-12-55

Comp. 5-11-54

County Ellis

KANSAS



CASING:

8 5/8" 132' cem. w/100 sx
 5 1/2" 3509' cem. w/125 sx

Elevation. 1987 DF

Production. 326 bbls. oil

Figures indicate Bottom of Formations.

shale & shells	325
sand	345
shale & shells	660
sand	870
shale	890
redbed & shells	1197
Anhydrite	1240
shale, shells & redbed	1645
shale & shells	1840
lime & shale	3000
lime	3210
lime & shale	3265
lime	3507
Arbuckle	3510
Total depth	

Tops :	
Heebner	3225
Toronto	3246
Lansing	3269
Arbuckle	3507

DST #1 3271-3305, open 30 min.
 fair blow 30 min. recovered 120'
 gas, 130' of oil and gas cut mud;
 BHP 880#, 20 min.
 DST #2 3315-3368, open 1 hr. strong
 blow 1 hour; recovered 2040 ft of gas
 on top of 480 ft. of heavily oil and
 gas cut mud:
 540' gassy oil, BHP 940#, 20 min.
 IFP 115#. FFP 410#.