


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

D. R. LAUCK, INCORPORATED &  
Company- H. H. BLAIR  
Farm- Geist No. 9

SEC. 27 T. 13 R. 17W  
SE NW NE

Total Depth. 3635'  
Comm. 11-14-55 Comp. 11-24-55  
Shot or Treated.  
Contractor. Carl Todd Drilling Company  
Issued. 4-13-57

County Ellis KANSAS



Elevation. 1992' DF

Production. 32 BOPD

**CASING:**

8 5/8" @140' w/125 sx cem.  
5 1/2" @3634' w/100 sx cem.

Figures Indicate Bottom of Formations.

shale	95
shale & shells	350
sand & shale	400
shale, iron & Red Bed	550
sand & shale	630
shale & shells	675
sand	875
shale & Red Bed	1180
shale	1215
Anhydrite	1245
shale & salt	1555
shale & shells	1880
lime	1965
shale & shells	2180
lime & shale	2390
shale & shells	2695
lime & shale	3090
lime	3100
shale & lime	3295
lime	3635 RTD
Total Depth	

TOPS	
Anhydrite	1215
Heebner	3259
Lansing	3304
Arbuckle	3551

**DRILL STEM TEST**

DST #1 3314-44 Op. 1 hr.  
closed in 20" rec. 65'  
watery mud. BHP 710#.  
DST #2 3353-74 Op. 1 hr.  
Rec. 10' mud, BHP 0#.  
DST #3 3562-90 Op. 1 hr.  
closed in 20" rec. 20'  
mud specked w/oil.  
BHP 195#.