


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- D. R. LAUCK OIL COMPANY
Farm- Geist No. 10

SEC. 27 T. 13 R. 17W
NW SE NW

Total Depth. 3872'
Comm. 5-31-56 Comp. 6-15-56
Shot or Treated.
Contractor. Carl Todd Drilling Company
Issued. 4-13-57

County Ellis KANSAS



Elevation. 1986' DF

Production. SWDW

Figures indicate Bottom of Formations.

shale & shells	665
sand	840
red bed & shale	845
shale & sand	1000
shale, shells	1205
Anhydrite	1240
shale, shells	1855
shale & lime	2160
lime	2230
lime & shale	3118
lime	3509
lime, shale, chert	3565
Conglomerate, cherty	3650
Conglomerate	
& chert	3697
lime & chert	3811
lime, chert,	
shale	3835
lime & shale	3861
lime	3872 RTD
Total Depth	

TOPS

Heebner	3250
Lansing/Kansas City	3295
Conglomerate	3535
Arbuckle	3675

DRILL STEM TESTS

DST #1 3300-3330 Weak blow
11 min. op by-pass, weak blow
6 min. Op. 1 hr. rec. 35' mud.
No show. BHP 0# in 20 min.
DST #2 3373-3402 Op. 1 hr.
fair blow decreasing to
very weak blow. Rec. 60'
slightly oil cut mud-few
specks free oil on top of
tool. BHP 575# in 20".
DST #3 3448-3480 Weak blow 5
min. by-pass tool, no help.
Op. 1 hr. rec. 22' mud.
BHP 0# in 20 min.