


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- D. R. LAUCK OIL CO., INC.
Farm- Geist No. 4

SEC. 27 T. 13 R. 17W
NE SE NW

Total Depth. 3531'
Comm. 3-27-54 Comp. 4-12-54
Shot or Treated.
Contractor.
Issued. 5-22-54

County Ellis KANSAS



CASING:

8 5/8" 160' cem w/100 sx
5 1/2" 3523 1/2' cem w/125 sx

Elevation. 1986' DF

Production. 120 BO & no wtr.

Figures indicate Bottom of Formations.

surface clay	40
shale & shells	560
shale, shells & sandstone	665
sand & shale	850
red bed & shells	1085
red bed & shale	1198
Anhydrite	1235
shale & shells	1940
lime & shale	2555
shale & shells	2885
shale & lime	3000
lime	3531 RTD
Total Depth	

Tops:

Topeka	2997
Heebner	3240
Toronto	3262
Lansing	3286
Arbuckle	3523

DRILL STEM TESTS:

#1 3342-3370, open 15 min., weak blow
12 min. and died; rec. 30' mud with
a few specks of oil; IFP 0#; FFP 0#;
BHP 500# 15 min.