


Company - DERBY OIL CO.
Farm - Weber No. 1.

SEC. 29 T. 13 R. 17 W
NEo NE

Total Depth. 3760
Comm. 2-17-45 Comp. 3-14-45
Shot or Treated.
Contractor. Crow Drlg. Co.
Issued. 3-31-45

County. Ellis
KANSAS



CASING:
8 5/8" 1324' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

surface clay shells	0-38
shale & shells	420
sand	479
shale & shells	693
shale	706
sand	815
shale & sand strks	888
red shale & shells	1000
lime brkn	1080
red shale & shells	1195
shale & shells	1246
anhydrite	1281
shale red	1300
shale w/anh. strks	1369
shale & shells	1489
red bed & shale	1660
salt	1790
salt & shale	1856
shale & shells	1894
lime & shale	1939
lime	1989
lime & shale	2136
shale red	2150
lime	2431
shale	2455
lime	2700
lime & shale	2941
lime brkn	3129
shale	3132
lime	3232
cherty lime	3255
lime	3560
conglomerate	3730
xlyn dolomite	3760
Total Depth.	

Tops:
Anhydrite 1240
Topeka 3062
Lansing 3343
Arbuckle 3731

Show of oil 3343-66