


Company - WILSON & WUNDERLICH
 Farm - Clarence Braun No. 1

SEC. 26 T. 13 R. 17W
 NE NE SW

Total Depth. 3542
 Comm. 8-14-49 Comp. 8-31-49 ✓
 Shot or Treated.
 Contractor. Tom Allan
 Issued. 9-24-49

County. Ellis
 KANSAS



and
 Elevation. 1955

Elevation. 1955

Production. dry

CASING:

1 1/4" 80' cem w/50 sx. circ.
 8 5/8" 1156' cem w/300 sx. circ.

Figures Indicate Bottom of Formations.

soil, sand	20
shale	250
sand, shale	850
red bed	1150
anhydrite	1188
red bed	1400
shale, anhydrite	1600
shale	1800
anhydrite	1900
shale	2078
lime	2170
lime cherty	2200
shale	2350
lime	2390
shale red	2414
lime oolitic	2424
shale, shells	2952
lime, shale brks	3085
lime lithographic	3096
lime, shale brks	3211
shale blk	3213
lime, shale	3250
shale red	3259
lime xlyn	3272
shale	3280
lime cherty	3288
shale	3300
lime	3313
shale	3322
lime	3334
lime cherty, residue	3340
lime	3348
lime sft oolitic	3355
lime	3370
shale	3380
lime cherty	3390
lime	3400
shale	3410
lime	3434
lime sft oolitic	3436
lime	3482
shale red	3490
lime	3497
shale red	3504
dolo. xlyn	3516
dolomite, oilstained	3518
dolo. sft (probably water)	2523
dolomite	3542
Total depth	

Tops:

Anhydrite	1150
Neva	2414
Lecompton	3085
Heebner	3211
Lansing	3259
Arbuckle	3504