


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING CO.
Farm- Rome No. 3

SEC. 27 T. 13 R.17W
SW SE NE

Total Depth. 3528
Comm. 9-20-53 Comp. 9-30-53
Shot or Treated.
Contractor. Murfin Drilling Co.
Issued. 1-30-54

County Ellis
KANSAS



CASING:
8 5/8" 120'
5 1/2" 3527'

Elevation. 1992' KB

Production. 1510 Bbls.

Figures indicate Bottom of Formations

shale & sand	40
shale	70
shale & shells	120
cement	120
shale & shells	340
sand	400
shale & shells	675
sand	830
shale & shells	970
sand Pyrite	980
red bed, shale, shell	1194
anhydrite	1233
shale, shells	1250
red rock, shale, shell	1580
shale, shells	1590
salt, shale	1800
shale, shells	1890
lime & shale	3255
lime	3340
lime & shale	3385
lime	3400
lime & shale	3525
lime & shale	3528
Total Depth	

TOPS:

Heebner	3236
Toronto	3256
Lansing	3282
Arbuckle	3525

D.S.T. #1 3302-3331 open
1 hr., good blow.thru-
out test, rec. 440'
salt wtr. BHP 850#,
FFP 175#.

D.S.T. #2 3361-3385 open
1 hr., rec. 160' sl.
OCGM, BHP 55#, FFP 40#