

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING CO.
Farm- Rome No. 6

SEC. 27 T. 13 R. 17W
SW NE NE

Total Depth. 3568

Comm. 8-25-55


Comp. 9-5-55

Shot or Treated.

Contractor. Murfin Drilling Co.

Issued. 1-28-56

County Ellis KANSAS



CASING:

8 5/8 125' w/ 100 sx cmt.
5 1/2 3554' w/ 100 sx cmt.

Elevation. 1991 DF

Production. 4 BOPH

Figures indicate Bottom of Formations.

shale		45
sand & shale		85
shale & shells		380
sand & shale		470
shale & shells		670
sand		860
red bed, shale & shells		1210
anhydrite		1246
shale & shells		1595
salt & shale		1820
shale, lime & shells		1930
shale & lime		3335
lime		3415
lime & shale		3535
Arbuckle lime	RTD	3565
lime		3568
Total Depth		

TOPS:

Heebner	3251
Lansing	3300
Arbuckle	3535

DST #1: 3554-65, open 1 hr. rec. 330'
gas, 120' VHO&GCM, 150' oil, BHP 855#