


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. GULF OIL CORPORATION
Farm. Anna B. Weber No. 5

SEC. 27 T. 13 R. 17W
NE NW SE

Total Depth. 3501
Comm. 11-26-53 Comp. 12-14-53
Shot or Treated.
Contractor.
Issued. 2-13-54

County Ellis
KANSAS



CASING:
8 5/8" 1198' cem. w/525 sx
5 1/2" 3500' cem. w/100 sx

Elevation. 1986' DF

Production. Pot. 1380 BO & NW

Figures indicate Bottom of Formations.

shale & shells	660
sand & shale	820
shale & shells	1000
red bed, strks	
pyrite	1135
red bed & shells	1181
anhydrite	1230
shale & shells	2045
shale & lime	2575
shale & lime strks	2745
lime & shale	3065
lime	3170
lime & shale	3230
lime	3501
Total Depth	

SCOUT TOPS:

Heebner	3212
Toronto	3233
Lansing	3257
Arbuckle	3498

Distance H: From top collar
to KB is 6.5'.

Acidized: W/500 gal. (12-14-53)

Sand Record: Arbuckle 3498