


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GULF OIL CORPORATION
Farm- Anna B. Weber No. 6

SEC. 27 T. 13 R. 17W
SE NW SE
1650' NSL & 1380' WEL

Total Depth. 3516'
Comm. 1-6-54 Comp. 1-31-54
Shot or Treated.
Contractor.
Issued. 4-17-54

County Ellis
KANSAS



CASING:

10 3/4" 1194' cem w/800 sx
7" 3507' cem w/100 sx

Elevation. 1281'

Production. Oil "P" 195 bbls.
Daily allowable 25 bbls.
(based on pumping test
65 bbls. oil in 8 hrs.)

Figures Indicate Bottom of Formations.

cellar	4
shale	660
sand	810
red bed	1010
red shale & pyrite	1130 ✓
red bed	1185
anhydrite	1230
shale & shells	1865
lime	1965
shale & lime	2095
lime	2340
lime & shale	2495
shale & lime	2550
lime & shale	2970
lime	3225
lime & shale	3266
lime	3516
Total Depth	

Tops:
Anhydrite 1185
Hoebner 3221
Toronto 3243
Lansing 3266
Arbuckle 3506

Distance H - 8.50' from top of collar on
10 3/4 csg. to top of KDB

Acidized w/500 gal. (before perf. w/TD 3511')
Perf. 3505-07' w/4 jet shots per ft.
(bottom 2' of 7" csg.)
Acidized w/1000 gal. XM-38 acid.
Sandfraced w/2100 gal. oil & 2000# sand.