


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- GULF OIL CORP.
 Farm- Anna B. Weber

No. 8

SEC. 27 T. 13 R. 17W
 SE NE SE
 1650' W of SL
 561' W of EL of SE/4
 County Ellis
 KANSAS

Total Depth. 3519'
 Comm. 3-4-54 Comp. 3-30-54
 Shot or Treated.
 Contractor.
 Issued. 5-29-54



CASING:
 8-5/8" 1186' w/550 sx cem.
 5-1/2" 35511' w/150 sx cem.

Elevation. 1985'

Production. 256 Bbls/ no wtr

Figures Indicate Bottom of Formations.

surface clay	60
sand	75
shale-shells	655
sand-shale stips	820
shale-shells	1180
anhydrite	1220
shale, shells-salt	1645
shale-lime	2210
lime	2315
lime-shale	2435
red bed	2442
shale	2445
shale-lime	2760
shale, sand-lime	2870
shale-shells	2990
lime-shale	3075
lime	3240
shale-lime	3275
limo	3504
limo-shale	3510
Arbuckle	3519
Total Depth	

TOPS: SCHLUMBERGER

Arbuckle	1187
Topeka	2975
Heebner	3219
Toronto	3238
Lansing	3268
Arbuckle	3509

Perf. 3399-3404' w/20
shots

Perf. 3349-3356' w/28
shots.

Perf. 3316-3320' w/16
shots.

Perf. 3293-3302' w/36
shots; acidized w/1000

Gal.

Treated open hole w/65
bbls. oil, 2000# sand
Squeezed off w/350 sx
cem.