


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS COMPANY
Farm - F.A. Schmidt No. 1

SEC. 16 T. 13 R. 17W
SEc SE

Total Depth. 3556'
Comm. 1-11-47 Comp. 2-3-47
Shot or Treated. Acidized.
Contractor. Kiowa Drilling Co.
Issued. 3-29-47

County. Ellis KANSAS



Elevation. 1976 ft.

Production. Pmpg. 449 BU, no
wtr.

CASING:

3-5/8" OD 1230' Cem. w/500 sx
5-1/2" OD 3550' Cem. w/175 sx

Figures Indicate Bottom of Formations.

surface clay & sand	0-102
shale & sand	200
shale	460
sand & shale	600
lime shells	630
sand & shells	675
sand	880
shale & shells	910
sand, shale & shells	1110
red bed & PT iron	1215
anhydrite	1250
sand & shale	1630
salt	1650
salt & shale	1750
shale & lime	2080
lime	2245
lime & shale	2275
lime	2460
shale & lime	2730
shale	2760
shale & lime	3010
lime	3045
shale	3055
lime	3556
Total Depth	

Tops:
Anhydrite 1215
Lansing 3297
Arbuckle 3543

Acidizing w/100 gal. acid,
filled up 5' w/oil- T.D. 3548'
Acidized w/500 gal. acid,
Max. Pressure 950#, Broke to
750# in 15 minutes. Broke to
275# in 5 minutes after acid
job.