

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 E. Murdock, Wichita, Kansas


Company - THE TEXAS CO.
 Farm - Schmidt No. 4

SEC. 16 T. 13 R. 17W
 SE NE SE

Total Depth. 3623
 Comm. 6-29-50 Comp. 7-14-50
 Shot or Treated.
 Contractor. Powell & Peters.
 Issued. 8-5-50

County. Ellis

KANSAS



CASING:
 10 3/4" 1250' cem. w/600 sx.

Elevation. 1996 D.F.

1718 Ind

Production. Dry

Figures Indicate Bottom of Formations.

sand & gravel	72
shale & gravel	100
shale & shells	340
sand	380
shale & shells	440
lime	485
sand & lime	510
shale & shells	590
sand	620
shale & shells	635
iron	650
shale & shells	700
sand	875
shale & shells	950
redbed	985
redbed & shells	1235
redbed	1240
anhyd.	1250
lime	1278
shale & shells	1996
lime	2500
lime & shale	2590
lime	2625
shale	2650
lime	2710
shale & lime	2850
lime	2970
lime & shale	3075
lime	3203
shale	3215
lime	3586
congl.	3599
shale & lime	3623
Total Depth	

Tops:	
Heebner	3274
Mansing	3319
Congl.	3566
Arb.	3587

7-11-50 Circ. at 3396-3416-3457 & 3492, no shows.
 7-13-50 Ran DST # 1 from 3593-3599. Open
 2 hrs., press zero, rec 5' mud. BHP 11# in
 15 mins.
 7-14-50 Ran DST #2 from 3593 to 3615. Tool
 open at 12:31 PM 7-13-50, blow air 10 mins.
 Closed tool at 2:31 PM, off bottom at 2:36 PM,
 800 # BHP, Rec. 33' of rotary mud.
 7-15-50 Plugged & abd.