


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Hardock, Wichita, Kansas

Company - THE TEXAS COMPANY
Farm - F. A. Schmidt No. 2

SEC. 16 T. 13 R. 17W
NW SE SE

Total Depth. 3578½
Comm. 12-6-49 Comp. 12-29-49
Shot or Treated.
Contractor. Stickle Drlg.
Issued. 1-28-50

County. Ellis
KANSAS



Elevation. 2011 feet

Production. 133.86 bbls oil in 8 hrs.

CASING:

8 5/8"	1253'	w/600 sx. cem.
5 1/2"	3576'	cem. w/100 sx.

Figures Indicate Bottom of Formations.

surface clay	40
sand	190
shale & shells	552
sand	650
shale	710
sand	850
shale & shells	1100
redbed	1243
anhyd.	1254
lime	1275
shale & shells	1760
salt	1860
shale	1905
shale & lime	2070
lime	2535
shale & lime	2615
lime & shale	2900
lime	3578½
Total Depth	

Tops:

Anhyd.	1243
Hoehner	3282
Lensing	3328
Arbuckle	3576

12-28-49 Bailed hole & tested casing.
Drilled cem. & shoe & cleaned out to bottom.
Hole filled up 700' w/oil in 3 hrs. Swabbed
45.14 bbls oil, no wtr in 12 hrs.

12-29-49 Drilled to 3578½' & acidized w/500
gals acid, max. press 700# PSI to vacuum.
Used 91 bbls of load oil. Swabbed back
load & swabbed 92.32 bbls. oil, no wtr
in 4 hrs.

12-31-49 Attempted to take draw down test
but well would not stabilize. Pumped 133.86
bbls of oil, .3 of 1% BS & wtr, in 8 hrs.