

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **A. SCOTT RITCHIE & HELLAR DRG., INC.**

SEC. 17 T. 13 R. 17W
 LOC. NW NE NE

FARM Staab "A"

NO2

COUNTY **Ellis**

TOTAL DEPTH **3593**

COMM. **4-15-66**


COMP. **4-25-66**

SHOT OR TREATED

CONTRACTOR **Hellar Drlg.**

ISSUED **6-18-66**

KANSAS



CASING

20	10	
15	8 5/8"	@ 215' w/135 sx.
12	6	
13	5 1/2"	@ 3587' w/100 sx.

ELEVATION **2010' KB**

PRODUCTION **PMP 163 BOPD**
NW GR 24.5 (Arb 3584-91)

FIGURES INDICATE BOTTOM OF FORMATIONS

0-215	Shale
215-967	Shale-shells-sand
967-1255	Red Beds & sand
1255-1293	Anhydrite
1293-1437	Shale & Lime Streaks
1437-1924	Shale & shells
1924-2174	Shale & Lime Streaks
2174-2935	Lime & shale
2935-3027	Shale
3027-3089	Topeka Lime
3089-3242	Lime
3242-3300	Lime & Shale
3300-3375	Lime
3375-3394	K.C. lime
3394-3450	Lime
3450-3476	K.C. lime
3476-3570	Lime
3570-3593	Shale & dolomite
3593	Rotary Total Depth

TOPS: SCOUT

Topeka	3043
Queen Hill	3209
Heebner	3287
Toronto	3307
Lansing	3331
Arbuckle	3583

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #2 Staab 'A', located in NW NE NE 17-13S-17W, Ellis County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas,
 this 2nd day of May, 1966