


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - TEXAS COMPANY
Farm - L. J. Drilling "B" No. 2

SEC. 21 T. 13 R. 17 W
SE NE SE

Total Depth. 3540' PB 3537½'
Comm. 5-21-47 Comp. 6-30-47
Shot or Treated.
Contractor. Kiowa Drlg. Co.
Issued. 8-16-47

County. Ellis
KANSAS



CASING:
8 5/8" 1210' Com. w/500 sx.
5½" 3519' Com. w/175 sx.

Elevation. 1962 feet

Production. Pumping 202 BO.

Figures Indicate Bottom of Formations.

surface clay	25
sand & shale	40
shale, shells & sand	185
shale & shells	300
sand	400
shale	550
shale & shells	660
sand	850
shale & shells	875
shale & iron	1040 ✓
red bed sdy	1160 ✓
red bed & iron	1195 ✓
anhydrite	1245
shale	1490
shale & limo	1625
shale & salt	1720
shale & shells	1880
limo & shale	1990
limo	2035
limo sdy & shale	2190
sdym limo	2225
limo	2315
shale & shells	2330
shale & limo	2475
limo	2550
shale	2560
limo	2605
limo & shale	2710
shale & shells	2780
limo	2815
shale	2840
limo	2910
shale & lime	2945
shale	2985
limo	3020
shale	3030
limo	3227
limo & shale	3280
limo	3540
Total Depth. PB 3537½'	

Tops:

Anhydrite	1195
Hoobner	3230
Lansing	3372
Arbuckle	3518

6-2-47 Ran DST Rec. 180' mud & salt wtr.
Packer set @ 3305'
6-16-47 Acidize w/500 gal. acid, pmpd 10 BOPH
6-18-47 Acidize w/1000 gal acid, pmpd 104½ BO,
no wtr., in 11 hrs.
6-22-47 Acidize 3530-35' w/500 gal. acid.
6-29-47 Acidize w/1000 gal. acid.