

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


Company - THE TEXAS COMPANY  
Farm. L.J. Dreiling "C" No. 2

SEC. 21 T. 13S R.17W  
NE SE NE/4

Total Depth. 3545'  
Comm. 6-17-47 Comp. 7-22-47  
Shot or Treated.  
Contractor. Kiowa Drilling Company  
Issued. 9-6-47

County. Ellis

KANSAS



Elevation. 1926 feet.

Production. 425 Bbls oil

CASING:

10 3/4" 1220' Cdn 500 sx  
7" 3532' Cdn 200 sx

Figures Indicate Bottom of Formations.

Surface clay & Sand	
Shale and shells	220
Sand and shale	275
Sand	390
Shale, Shells & Sand	520
Shale and shells	670
Sand	865
Shale	890
Red bed and Iron	990
Red shale, Shells & Iron	1125
Red Bed and iron	1210
Anhydrite	1220
Anhydrite	1255
Shale	1575
Lime and Shale	1620
Salt	1670
Salt and shale	1695
Lime and shale	1995
Lime	2030
Lime and shale	2155
Sand and Shale	2185
Lime	2250
Lime and shale	2485
Lime	2500
Lime and shale	2665
Shale and lime	2935
Shale	2990
Lime and shale	3015
Lime	3250
Shale and Lime	3290
Lime	3534
Lime	3542
Total Depth	

Remarks:

7-10-47 Acidize with 500 gal.,  
maximum pressure, casing 850# tubing  
750#. Swab 35 Bbl oil in one hour.

7-19-47 Acidized with 1000 Gal.

Tops:	
Anhydrite	1210
Heebner	3242
Lansing	3284
Arbuckle	3530

SSO:	
3372 - 83	
3383 - 90	
3410 - 20	
3450 - 70	
3500 - 15	