

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS COMPANY
Farm - L. J. Dreiling "C" No. 1

SEC. 21 T. 13 R. 17W
Sec NE

Total Depth. 3543'

Comm. 4-8-47


Comp. 5-1-47

Shot or Treated. Acid.

Contractor. Kiowa Drilling Co.

Issued. 5-31-47

County. Ellis KANSAS



Elevation. 1974 feet

Production. Pmpg 502 BO, no wtr

CASING:

8-5/8" OD 1220' Cem. w/500 sx
5-1/2" OD 3533' Cem. w/175 sx

Figures Indicate Bottom of Formations.

surface, clay & sand	0-40
shale & shells	300
sand	345
shale & shells	435
sand & shale	500
shale & shells	670
sand	850
red bed & iron	1050
red bed & sand	1080
red bed & iron	1200
anhydrite	1250
shale	1275
red bed	1320
shale & shells	1600
salt	1700
shale	1870
shale & lime	2135
lime sdy	2490
lime & shale	2650
shale & shells	2710
shale " lime	2990
lime	3110
lime & shale	3165
lime	3190
lime & shale	3280
lime	3315
lime & shale	3350
lime	3543
Total Depth	

Tops:

Anhydrite	1200
Lansing	3290
Arbuckle	3533

Remarks:

SS oil 3387-90'-4/22/47, ran
Schlumberger- 4/29/47. Dumped
100 gal acid to clean up hole,
drilled 3536 to 38', no oil.
Drilled 3538-41', 10 gal oil
per hr. Drilled 3541-43', filled
up 1500' in 1 hr. Swabbed 126 BO
no wtr in 9 hrs-Acid. w/500 gal acid.