

One copy of all wireline logs and drillers time log shall be attached with this form. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

SIDE TWO

Operator Name D-Oil, Inc. Lease Name..... Schneidler Well #..... 1

Sec. 21 Twp. 13 Rge. 17 ☐ East
☒ West County..... Ellis

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

.....

Drill Stem Tests Taken ☐ Yes ☒ No
 Samples Sent to Geological Survey ☐ Yes ☒ No
 Cores Taken ☐ Yes ☒ No

Formation Description
☒ Log ☐ Sample

Name	Top	Bottom
Anhydrite	1225	1262
Topeka	3004	
Heebner	3245	
Toronto	3266	
Lansing KC	3289	
Base	3523	
Arbuckle	3535	
RTD	3598	

	Oil	Gas	Water	Gas-Oil Ratio	Gravity
Estimated Production Per 24 Hours	21 Bbls	MCF	12 Bbls	CFPB	

METHOD OF COMPLETION

Production Interval

Disposition of gas: ☐ Vented ☐ Open Hole ☒ Perforation
☐ Sold ☐ Other (Specify)
☐ Used on Lease

3264-3548 Overall

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface Production	12 1/4" 7 7/8"	8 5/8" 5 1/2"	24# 14#	218' 3597'	q-set thriftly-mix common	140 400 100	

PERFORATION RECORD

Acid, Fracture, Shot, Cement Squeeze Record
(Amount and Kind of Material Used)

Shots Per Foot	Specify Footage of Each Interval Perforated	Depth
2	3542-48	1,250 Gals. 15%
1	3525-29, 3516-22, 3493-3503, 3466-74, 3452-60, 3424-30, 3382-90, 3356-64, 3337-45, 3314-20, 3294-30, 3264-70	5,250 Gals. 15%

TUBING RECORD	Size	Set At	Packer at	Liner Run	☐ Yes ☐ No
	2 3/8"	3570			

Date of First Production Producing Method
☐ Flowing ☒ Pumping ☐ Gas Lift ☐ Other (explain).....