

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company- BELL BROTHERS
Farm- Von Lintel No. 1

SEC. 26 T. 13 R. 17W
SW SW NW

Total Depth. 3518
Comm. 12-1-52 Comp. 1-14-53
Shot or Treated. Acid: 500 gals.
Contractor. Murfin Drilling Co.
Issued. 3-14-53

County Ellis

KANSAS



CASING:

8 in. 127'
5 in. 3518'

Elevation. 1983 DF

(1986 (and))

Production. Drawdown 2710 bbls.

Pot. no water

Figures indicate Bottom of Formations.

shale	35
sand & shale	70
shale & shells	310
sand	370
shale & shells	660
sand	835
red bed & shells	1070
red bed & shale	1183
anhydrite	1229
shale	1240
shale & shells	1595
salt & shale	1815
shale & shells	1995
lime & shale	3125
lime	3290
lime & shale	3380
lime	3430
lime & shale	3518
Total Depth	

TOPS:	
Anhydrite	1183
Heebner	3226
Kansas City	3274
Arbuckle	3515

SJ TOPS:	
Topeka	2978
Heebner	3223
Toronto	3242
Lansing	3271
Base KC	3494
Arbuckle	3512

3322-24 stain
3339-41 stain
3348-52 stain, odor
3364-67 porosity, no show
3512-15 good odor, some free oil,
light staining.

Electric Log total depth 3515.

Schlumberger and SLM showed T. D.
and all tops to be 3' higher than
driller's depths