



# LOG OF WELL

SHEET No. 2

21-13-17w  
p2

District **Kansas** Owner **The Texas Company Farm L.J. Drilling "C" Well No. 2**

FORMATION	AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
face clay & sand	45				ELEVATION....1978 KB  TOPS: Anhydrite.....1210 Heebner.....3242 Lansing.....3284 Arbuckle.....3530  CASING RECORD: 10-3/4" Csg. set at 1220' w/500 sax Lone Star cement & 200 # CC. 7" Csg. set at 3532' w/200 sax Lone Star Cement.  SSD: 3372 - 83 3383 - 90 3410 - 20 3450 - 70 3500 - 15
le and shells	220 175				
l and shale	275 55				
d	390 115				
le, shells & sand	520 130				
le and shells	670 150				
d	865 195				
le	890 25				
be and iron	990 100				
Sh e, shells & Iron	1125 135				
be and iron	1210 85				
ydrite	1220 10				
ydrite	1255 35				
le	1575 320				
e and shale	1620 45				
t	1670 50				
t and shale	1695 25				
e and shale	1995 300				
e	2030 35				
e and shale	2155 125				
d and shale	2185 30				
e	2250 65				
e and shale	2465 235				
e	2500 15				
e and shale	2665 165				
le and lime	2935 270				
le	2990 55				
e and shale	3015 25				
e	3250 235				
l and lime	3290 40				
e	3534 244				
e	3542 8				

AL, DEPTH 3542

**REMARKS:**

7-10-47 Acidize w/500 gal., maximum pressure, casing 850# tubing 750#. Swab 35 Bbl oil in one hour.  
 7-19-47 Acidized with 1000 Gal.