


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NADEL & GUSSMAN
Farm- Leikam "A" No. 2

SEC. 2 T. 13 R.17W
C E/2 SE NW

Total Depth. 3575'
Comm. 2-3-59 Comp. 2-13-59
Shot or Treated.
Contractor. Reserve Drlg.
Issued. 7-4-59

County Ellis
KANSAS



Elevation. 2051' DF

Production. 82 BOPD

CASING:

3 5/8" 215' cem w/150 sx.
5 1/2" 3571' cem w/150 sx.

Figures indicate Bottom of Formations.

shale	735
sand	915
shale	1015
shale & shells	1225
Anhydrite	1270
shale	1310
shale & shells	1850
lime & shale	2240
lime	2345
shale	2520
shale & lime	3140
lime	3575
Total Depth	

TOPS:

Anhydrite	1225
Heebner Shale	3260
Toronto Lime	3282
Lansing	3308
Base Kansas City	3500
Arbuckle	3572

DST #1 3226-63', op 45 min., weak blow
22 mins. rec. 30' mud. BHP 980#/30 mins.

DST #2 3315-45', op 30 min., weak blow for
6 mins., rec. 30' mud. BHP 100#/30 mins.

DST #3 3348-70', op 1½ hrs, fair blow,
rec. 55' heavy oil cut mud. BHP 260#/30 mins.
(Building)

DST #4 3371-96', op 1 hr., strong blow.
rec. 100' muddy oil & trace water.
BHP 585#/30 mins.

DST #5 3458-3506', op 1 hr, good blow -
rec. 800' gas plus 265' gassy oi.
BHP 1110#/30 mins.