


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NADEL & GUSSMAN
Farm- Staab "A" No. 1

SEC. 2 T. 13 R. 17W
NW NW SE

Total Depth. 3605'
Comm. 5-1-58 Comp. 5-10-58
Shot or Treated.
Contractor. Reserve Drlg.
Issued. 6-28-58

County Ellis
KANSAS



CASING:
8 5/8" 206' cem w/150 sx.

Elevation. 2049' DF

Production. Dry

Figures Indicate Bottom of Formations.

shale	515
shale & shells	755
sand	930
red bed	1222
anhydrite	1260
shale	1270
shale & shells	1995
shale & lime	3175
lime	3245
lime & shale	3300
lime	3605 RTD
Total Depth	

TOPS:	
Heebner	3269
Toronto	3290
Lansing	3316
Base Kansas City	3548
Conglomerate Chert	3577

DST #1 3331-50', op 1½ hrs, weak blow,
rec. 60' gas plus 25' cem. BHP 30#/30 mins.

DST #2 3352-80', op 30 min, weak blow,
for 9 min, rec. 10' mud. BHP 0#.

DST #3 3376-98', open 2 hrs, weak blow,
rec. 3' muddy oil plus 30' muddy salt
water. BHP 390#/30 mins.