

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg, Wichita, Kansas.

GULF OIL CORP.
B. F. Messick No. 1.

SEC. 3 T. 13 R. 17W.


SW 1/4 SE

Plotted Texas CO.

County Ellis

Total Depth. 3428
Comm. 12-13-36 Comp. 2-1-37
Shot or Treated. 1-23-37 2000 Gal. 1-28-37 5000 gal.
Contractor.
Issued. 4-10-37

APR 10 1937



CASING.

15 1/2" 148'
7" 3271'
5 1/2" 91' liner set at 3340

Elevation.

Production. Pot. 432 B.
31 BW.

Figures Indicate Bottom of Formations.

shale and shells 250
shale 410
sand 470
shale and shells 507
broken sand 610
shale and shells 710
sand sft & shells 840
shale blue 857
shale & sand 895
shale & shells 1040
red bed 1110
lime broken 1218
lime 1230
shale & shells 1440
shale & salt 1560
shale & shells 1850
lime broken 1880
shale & shells 1904
broken lime 1936
shale and lime
shells 1985
lime 2030
lime broken 2181
lime 2328
lime broken 2488
broken lime and
shale 2573
broken lime 2640
lime hard 2645
shale and lime 2690
shale 2880
broken lime 2948
dhale 2970
lime 2988
broken lime 3038
lime 3125
Topoka lime 3140
lime hard 3154
lime 3230
broken lime 3255
shale & lime 3258
broken lime 3268

shale 3271
lime 3276
shale 3282
Oswald lime 3287
lime 3303
red rock 3506
lime 3323
shale blue 3328
lime 3332
shale 3336
lime 3348
shale 3353
lime 3390
shale 3400
lime 3423
shale 3428

Total Depth.

Oswald lime 3271 to 3428