

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS COMPANY
Farm - L. J. Drilling "E" No. 2

SEC. 22 T. 13 R. 17W
S. 1 SW NW

Total Depth. 3577'
Comm. 9-6-47 Comp. 9-30-47
Shot or Treated. Acidized
Contractor. Klowa Drilling Company
Issued. 12-27-47

County. Ellis
KANSAS



CASING:
8-5/8" 1235' Con. W/500 Ss.
5-1/2" 3556' Con. W/175 Ss.

Rotary tools used from 0 to 3556'
Cable tools used from 3556' to 3577'

Elevation. 1995' *sh*

Production. Pumpd 77 Bbls oil.

Figures indicate Bottom of Formations.

surface clay &	
most rock	46
shale & shells	310
sand	400
shale	495
shale & shells	685
sand	870
shale	875
shale & shells	1225
Arbuskle <i>Arbuskle</i>	1270
shale & shells	1620
salt & shale	1785
shale & shells	1875
lime broken	1975
lime	2040
lime & shale	2080
shale	2135
lime & shale	2185
lime brkn & sdy	2245
lime & shale	2310
lime	2425
lime broken	2495
lime	2520
lime & shale	2655
lime broken	2710
lime	2750
shale	2815
shale & lime	2880
lime broken	2960
shale	3035
lime	3400
lime cherty	3470
lime	3577

Total Depth

TOPS:

Arbuskle	1225
Hoebner	3267
Lansing	3314
Arbuskle	3552

9-20-47 Running Schlumberger Survey

9-26-47 Still show oil 2564'

9-27-47 Bailing 40 gal. oil per hr. Acid W/500 gal.

9-28-47 Swabbed 2 bbl oil per hr. Reacidized W/1000 gal acid thru casing. Max press 1050#. Dropped to 650# during treatment. After acid in form, press dropped 400# in 5 min. Drpd. to 0 in the next 5 minutes.

9-29-47 Swabbed down after acidizing. Tested for 10 hrs, 20 bbls.