

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- GRAHAM-MESSMAN-RINEHART OIL CO.
Farm- Wolf "A" No. 2

SEC. 4 T. 13 R. 17W
NE SE SW

Total Depth. 3633
Comm 5-10-55 Comp. 5-18-55
Shot or Treated.
Contractor. G-M-R Drilling Co.
Issued. 6-25-55

County Ellis

KANSAS



Elevation. 2061 KB

Production. 200 BOPD

CASING:

8 5/8 @ 202' w/ 125 sx cmt.
5 1/2 @ 3555' w/ 60 sx cmt.

Figures indicate Bottom of Formations.

clay & sand	100
shale	203
shale & shells	410
sand & shale	760
sand	900
shale & red bed	1240
anhydrite	1290
red bed & shale	1570
shale & shells	1660
salt	1850
lime & shale	2450
shale & shells	2500
lime & shale	3365
lime	3535
lime & conglomerate	3633
Total Depth	

TOPS:

Anhydrite	1246
Topeka	3025
Heebner	3273
Toronto	3294
Lansing	3342
Conglomerate	3578