

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 E. Hurdock Wichita, Kansas

Company - W. L. HARTMAN
Farm - Wolfe "B"

No. 2

SEC. 4 T. 13
NE NW SW

17W

Total Depth.

3589

3689

Comm. 12-27-49

Comp.

1-20-50


Shot or Treated.

Contractor. H. & H. Drilling

Issued. 2-11-50

County. Ellis

KANSAS



Elevation. 2055 Ind

Production. D & A

CASING:

8 5/8" at 125' cen w/ 110 sx's

Figures Indicate Bottom of Formations.

clay and shale	125
shale	530
sand and shale	760
sand	895
shale shell & sand	1251
anhydrite	1291
shale and sand	1662
shale and shell	1905
lime	2035
lime and shale	2323
lime	2415
lime and shale	2549
lime	2781
lime and shale	2915
lime	2967
lime and shale	3210
lime	3330
lime and shale	3405
lime	3612
certy conglomerate	3673
congl. and arbuckle	3689
Total Rotary Depth	

Tops: (Derrick floor data- corrected
2 foot for rotary bushing)

Anhydrite	1249
Topeka	3048
Heebner shale	3301
Dodge lime	3326
Lansing-Kans City	3347
Marmaton	3579
Seoy Conglomerate	3595
Simpson Shale	3677
Arbuckle	3683

Geological Data:

Drill Stem Test #1 3436-3450 open 30 mins-
weak blow 15 mins. Rec. 5' mud BHP 0"

Circ. 3365 - no odor

Circ. 33450 - no odor & 3470- no odor

Circ. 33532, 3600, 3610, 3616, 3629,
3645, 3651- no odor in samples. Trip
3651'

Circ. 33669, 3679, 3689- no odor D&A