


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING CO.
Farm- Karlin "B" No. 2

SEC. 5 T. 13 R. 17W
NE SE NE

Total Depth. 3640'
Comm. 4-11-56 Comp. 4-20-56
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 6-9-56

County Ellis
KANSAS



CASING:
8 5/8" 108' cem w/90 sx

Elevation. 2076' KB

Production. Dry

Figures indicate Bottom of Formations.

clay	40
sand	55
shale	590
sand	710
sand and shale	800
sand	920
red rock	1270
anhydrite	1300
red rock	1690
salt	1820
shale and shells	2060
lime	2420
lime and shale	2790
shale and shells	3050
shale and lime	3385
lime	3590
lime and shale	3606
Conglomerate	3640
Total Depth	

Tops:

Anhydrite	1270
Heebner	3309
Toronto	3328
Lansing	3356
Conglomerate	3606

DST #1 3383-87', open 1/2 hr., weak blow 9 min.
Flushed tool, wk. bl. 4 min., Rec. 30' mud
BHP 905# in 15 min.

DST #2 3426-45', open 1 hr., wk. interm. bl.
Rec. 50' watery mud. BHP 225# in 20 min.