

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas


Company - W. L. HARTMAN & J. B. HINKLE
Farm - Reed No. 1

SEC. 5 T. 13 R. 17W
NW NW SE

Total Depth. 3621
Comm. 6-22-49 Comp. 7-16-49
Shot or Treated.
Contractor.
Issued. 9-10-49

County. Ellis

KANSAS



Elevation. 2049

Production. 47 BOPD

CASING:

8 5/8" 138' cem. w/120 sx.
5 1/2" 3596' cem. w/125 sx.

Figures Indicate Bottom of Formations.

shale & sand	138
shale	250
shell & shells	405
shale & sand	755
Dakota sand	925
shale	1000
D.C. Sand	1125
shale & sand	1275
shale	1280
anhyd.	1316
shale & shells	1700
salt, shale & shells	1905
shale & lime	2150
shale	2300
lime & shale	2530
lime	2656
lime & shale	3057
lime	3275
lime & shale	3406
lime	3578
lime & shale	3595
lime	3621
Total Depth	

Tops: D. F.	
Topeka	3040
Heebner	3292
Dodge	3315
Gansing-K.C.	3337
Marmaton	3566
Simpson	3593
Arbuckle	3595
R.T.D.	3601

Trip at 2197
" " 2533
Circ. @ 3050 & 3057
" @ 3126
" @ 3266
" @ 3389 & 3406

DST at 3040-57' Got 8' rotary mud in 30 mins.
" at 3380-3404 Open 15 mins. Rec. 75'
oil & gas cut mud, trace
clear wtr.
" at 3426-39, open 1 hr. Rec. 55' mud which
was oil & gas cut. Fair odor
no wtr.
Circ. @ 3600-3603 RTD 3603'
" @ 3598-3601 trace free oil, no odor