


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ELBORADO REFINING CO.
Farm- Braun No. 3

SEC. 34 T. 13 R. 17W
NE NE NE

Total Depth. 3533
Comm. 10-23-51 Comp. 11-26-51
Shot or Treated.
Contractor. Pickrell Drlg. Co.
Issued. 1-5-52

County Ellis
KANSAS



CASING:

8 5/8" 352' cem w/180 sxs.
5 1/2" 3510' cem w/100 sxs.

Elevation. 1978 DF

Production. 50 BOPD

Figures Indicate Bottom of Formations.

sand, shale, shells	175
shale, shells	600
iron	650
sand	805
red rock, shale	885
shale, shells	1028
anhydrite	1050
shale, shells	1820
lime	1955
lime, shale	2135
lime	2450
lime, shale	2760
lime	3510 RTD
lime	3533
Total depth	

Tops: DF
Heebner 3212
Toronto 3228
Lansing 3260
Arbuckle 3502
No. Cg.

DST 3270-90, op. 1 hr. rec.
58' muddy salt wtr.,
slight blow/ 1 hr. BHP 928#
DST 3318-40, op. 1 hr.
rec. 8' mud, 4' FO light
blow BHP 50 # 15 min. &
building up
DST 3388-3400, op 1 hr. rec.
45' sli. OCM, BHP 80#/15 min.
C. O. to RTD odor no show;
D D 3525; S O 3522-25 1 blr.
per hr. D D 3528, 1/2-2/3 BOPH;
DD 3533, increase in oil 3529 1/2-
33; ϕ 1 1/2 BOPH/2 hrs. 500
acid ϕ 2 1/2 BOPH/5 hrs.

MIMIO BOND
MADE IN U.S.A.