

KL

24-13-18W

copy
State Geological Survey
of Kansas

CONTRACTOR'S WELL LOG

OPERATOR: K & E Petroleum, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: KIPPES #1
 LOCATION: 50' W of NW SE NE, Section 24-13S-18W
 Ellis County, Kansas
 START DATE: 07-28-80
 COMPLETION DATE: 08-05-80

0	1712	Sand & Shale
1712	3713	Shale & Lime
	3713	Rotary Total Depth

Drilled hole at 5:00 p.m. 07-28-80. Drilled 578' of a 12-1/4" hole. Ran 15 joints of 8-5/8" - 20# casing (tally 568'). Set at 574.50'. Cemented with 150 sx. of 50/50 posmix, 2% gel, 3% c.c. Followed with 150 sx. of common, 2% gel, 3% c.c. Plug was down at 5:30 a.m. 07-28-80. Cement and circulate.

T.D. 3713'. Ran 89 joints of 4-1/2" - 10-1/2" casing (tally 3695.77'). Set at 3699.77'. Cemented with 150 sx. of 50/50 posmix salt saturated. Ran 20 barrels salt flush ahead of cement, followed with 200 sx. of light 2% gel. Cement by Sun Cementing. Plug was down at 3:00 p.m. 08-05-80.

SAMPLE TOPS:

Anhydrite 1363'
 Anhydrite 1405'

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 22 1980
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KIPPES #1 ' W of NW SE NE, Section 24-13S-18W, Ellis County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas.