

25-13-18w


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CLINTON OIL CO.
Farm- Gross "D" No. 4

SEC. 25 T. 13 R. 18W
SE SE SE

Total Depth. 3651'
Comm. 5-11-64 Comp. 5-20-64
Shot or Treated.
Contractor. Garvey Drilling Company
Issued. 10-3-64

County Ellis
KANSAS



Elevation 2067' DF

Production, Dry

CASING:

8 5/8" 226' cem w/150 sx.
5 1/2" 3613' cem w/110 sx.

Figures Indicate Bottom of Formations.

surface clay	20
clay & shale blue	226
shale	500
redbed & shells	770
sand	960
shale	1115
shale & gypsum strks.	1303
Anhydrite	1342
shale & shells	1675
shale & lime	1960
lime	2001
shale & lime	2190
lime	2570
lime & shale	2712
shale & lime	3095
lime & shale	3260
lime	3651 RTD
Total Depth	

TOPS: LOG

Anhydrite (sample)	1303
Heebner	3316
Toronto	3335
Lansing Kansas City	3362
Base Kansas City	3588
Arbuckle	3612