

10-13-19W

DRILLERS' WELL LOG

DATE COMMENCED: April 24, 1979
DATE COMPLETED: May 2, 1979

Raymond Oil Co., Inc.
MERMIS # 3
C N/2 SE NW
Sec.10-T13S-R19W
Ellis County, Ks.

State Geological Survey
WICHITA, BRANCH

0 - 870' Surface Soil, Shale
870 - 1070' Sand
1070 - 1388' Shale
1388 - 1429' Anhydrite
1429 - 3100' Shale & Lime
3100 - 3342' Lime
3342 - 3345' Shale
3345 - 3386' Lime & Shale
3386 - 3426' Lime
3426 - 3675' Lime & Shale
3675' RTD

ELEVATION: 2075 K.B.

FORMATION DATA	
Anhydrite	1388
Topeka	3100
Heebner	3342
Toronto	3364
Lansing	3386
Base K.C.	3426
RTD	3675

SURFACE PIPE: Ran
used 10 3/4", 36#
pipe @ 225' w/125
sacks common cement
2 % gel, 3 % cc.

RECEIVED
STATE CORPORATION COMMISSION

MAY - 4 1979

CONSERVATION DIVISION
WICHITA, KANSAS

PRODUCTION PIPE: Ran
used 4 1/2" pipe, 10 1/2 #
@ 3662' w/150 sacks
pozmix, 7 1/2 % salt;
2 stage @ 1380' w/300
sacks Howco Light cement.

A F F I D A V I T

State of Kansas
County of Barton) ss.

Bill Draney, of lawful age does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 3 day of May, 1979