

13-13-17W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY D. G. HANSEN TRUST

SEC. 13 T. 13 R. 19W
LOC. SW NW NE

FARM Sack NO. 1

COUNTY Ellis

TOTAL DEPTH 3735'


COMM. 8-8-68

COMP. 8-16-68

SHOT OR TREATED

CONTRACTOR C-G Drlg.

ISSUED 10-5-68



CASING

20	10	
15	8	5/8" 187' cem w/ 150 sx
12	6	
13	5	

ELEVATION 2072' KB

PRODUCTION DRY/ARB

FIGURES INDICATE BOTTOM OF FORMATIONS

0	187	SAND
187	830	SHALE & SAND
839	990	SAND
990	1369	SHALE & RED BED
1369	1414	ANHYDRITE
1414	1810	SHALE
1810	2030	SHALE & SHELLS
2030	3250	LIME & SHALE
3250	3690	LIME
3690	3707	ARBUCKLE
3707	3735	TOTAL DEPTH

$\frac{1}{4}$ @ 500'
 $\frac{1}{2}$ @ 1040'
 $\frac{1}{4}$ @ 1530'
 $\frac{3}{4}$ @ 2000'

DST #1 3558-3580
OPEN 15 SHUT IN
30 OPEN 30 SHUT IN
30 REC 10' MUD FEW
SPECKS OIL
DST #2 3710'-3720'
OPEN 30 SHUT IN 30
OPEN 30 SHUT IN 30
REC 5' FREE OIL
60' OIL CUT MUD

TOPS: SMP
Anhydrite 1369
Toronto 3366
Lansing 3394
Base Kansas City 3643
Conglomerate 3690
Arbuckle 3707
TD 3735