

Operator ENERGY RESERVES GROUP, INC. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: DRY HOLE

Well No. #8 Lease Name PFEIFER

S 19 T 13S R 19W E W

WELL LOG
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 3172-3212 UPPER TOPEKA 30-60-60-120 IF 27-44, FF 44-88, ISIP 968, FSIP 968. Rec. 150 WM			ANHYDRITE	1432 (+678)
			BASE ANHYDRITE	1476 (+634)
DST #2 MISRUN			TOPEKA	3151 (-1041)
DST #3 3340-80 LOWER TOPEKA IFP 9-9, ISIP 1083, FFP 9-18, FSIP 1075. Weak blow. Rec. 30' mud.			HEEBNER	3391 (-1281)
			TORONTO	3415 (-1305)
DST #4 L-KC "A" & "B" zones 3418-70' MISRUN			LANSING	3435 (-1325)
			BASE KANS. CITY	3688 (-1578)
DST #5 3428-70' L-KC "A" & "B" zones. IFP 36-45, FFP 45-34, ISIP 495, FSIP 495. Rec. 40' mud.			MARM. CHERT	3728 (-1618)
DST #6 3488-3540 L-KC "F" & "G" zones. IFP 18-79, FFP 79-162, ISIP 563, FSIP 555. Rec. 380' MSW				
Plugged, dry hole, RTD 3832 04/07/80				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>John B. Mullen</i>
	JOHN B. MULLEN DISTRICT GEOLOGIST
	Signature Title
	JUNE 19, 1980
	Date