

19. 13. 17W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **CLINTON OIL**

SEC. 19 T. 13 R. 19W
 LOC. NW SW NE

FARM **Pfeifer**

NO. **3-D**

TOTAL DEPTH **3856**

COMM. **8-3-66**

COMP. **8-14-66**


SHOT OR TREATED

CONTRACTOR **Garvey Drlg.**

ISSUED **10-8-66**

COUNTY **Ellis**

KANSAS



CASING

20	10		
15	8 5/8"	@ 212'	w/175 SX
12	6		
13	5 1/2"	@ 3855'	w/700 SX

ELEVATION **2148'KB**

PRODUCTION **PMP 50 BOPD @**
247 BWPD (Lans 3651-57)

FIGURES INDICATE BOTTOM OF FORMATIONS

TOPS: **SCOUT**

*Anhydrite	1480-1522	45' Post Rock
Topeka	3177	150' Blue Shale and Shells
Heebner	3425	212' Blue Shale
Toronto	3446	955' Shale and Shells
Lansing	3467	1160' Sand
" "B"	3498	1480' Shale and Shells
" "D"	3515	1522' Anhydrite
" "F"	3540	1970' Shale and Shells
" "G"	3559	2110' Shale
" "H"	3603	2485' Lime with Shale
" "I"	3626	3330' Shale and Lime
" "J"	3648	3445' Lime with Shale
" "K"	3675	3856' Lime
" "L"	3703	3856' RTD
Base Kansas City	3721	
Marmaton Lime	3740	
Chert	3758	
Arbuckle	3827	

State of **Kansas**

County of **Barton**