

17. N. 17W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- JONES-GEBERT OIL, INC & CLINTON OIL
Farm- Pfeifer No. 2

SEC. 19 T. 13 R. 19W
NW NE NW

Total Depth. 3890'
Comm. 3-24-64 Comp. 4-7-64
Shot or Treated.
Contractor. Jones-Gebert Oil, Inc.
Issued. 6-6-64

County Ellis
KANSAS



Elevation. 2179' KB

Production. DRY

CASING:
8 5/8" 206' cem w/ 135 sx

Figures Indicate Bottom of Formations.

post rock	40	
shale	80	
shale & shells	210	
shale	460	
shale, clay beds, blue	1325	
shale & shells	1511	
anhydrite	1529	
shale	2020	
lime & shale	2460	
lime w/shale streaks	2585	
lime & shale	3339	
lime	3463	
lime & shale	3500	
Lansing lime	3520	
lime	3548	
Lansing	3585	
lime	3613	
lime & shale	3670	
lime	3754	
lime & shale	3808	
lime	3838	
lime & shale Dolomite	3870	
lime	3890	RTD
Total Depth		

TOPS :SCOUT	
Anhydrite	1511
Topeka	3204
Heebner	3458
Toronto	3481
Lansing	3501
Base Kansas City	3745
Marmaton	3762
Marmaton Chert	3794
Arbuckle	3854