

CEMENTING LOG

24-13-19W
STAGE NO.

24-135-19W 4950 FSL + 1155 FCL

12-17-85 District 0133104 Ticket No. 252664
Company R P Nixon Rig
Case EQD Well No. 1-B
County Ellis State KS
Location Field

ASING DATA: PTA ☐ Squeeze ☒
Surface ☐ Intermediate ☐ Production ☐ Liner ☐
Size 4 1/2 Type J 35 Weight 9.00 Collar 8 Rond
2 3/4 J 55 4.60 8 Rond

asing Depths: Top Bottom

ill Size Weight Collars
en Holes Size 7 7/8 T.D. Collar 1245 ft. P.B. to 1245 ft.

PACIFIC ACTORS:
sing: Bbls/Lin. ft. 0.0163 Lin. ft./Bbl. 11.5380
en Holes: Bbls/Lin. ft. Lin. ft./Bbl.
H P Bby Bbls/Lin. ft. 0.0037 Lin. ft./Bbl. 258.6451
nulus: 5 1/2 C Bbls/Lin. ft. 0.0109 Lin. ft./Bbl. 92.8449
sing: 1 1/2 Bbls/Lin. ft. 2.0568 Lin. ft./Bbl. 17.5921
forations: Forms ft. to ft. Amt.

MPANY REPRESENTATIVE *Leon J. Garcia*

CEMENT DATA:

Scavenger Type:
Amt. Sks Yield ft³/sk Density PPG
LEAD: Pump Time hrs. Type Class A + F
50/150 Poz 6 1/2 G. 1 Excess
Amt. 350 Sks Yield 1.53 ft³/sk Density 13.3 PPG
TAIL: Pump Time hrs. Type
Excess
Amt. Sks Yield ft³/sk Density PPG
WATER: Lead gals/sk Tail gals/sk Total Bbls.

Pump Trucks Used
Bulk Equip.

Float Equip: Manufacturer
Shoe: Type Depth
Float: Type Depth
Centralizers: Quantity Plugs Top Btm.
Stage Collars
Special Equip.
Disp. Fluid Type water Amt. 4 1/4 Bbls. Weight 8.34 PPG
Mud Type Weight PPG

CEMENTER *M. E. Welf*

TIME	PRESSURES PSI		FLUID PUMPED DATA			REMARKS
	DRILL PIPE CASING	ANNULUS	TOTAL FLUID	Pumped Per Time Period	RATE Bbls/Min.	
						Set Brig Plug at 1505 Load with salt water Test Plug to 1500 Lbs Open port Collar Check for Circulation Mix 350 Sks 50/150 Poz 6 1/2 G. 1
1:00	500	500	28	8 Min	3.5	Time start Loading Hole Time Test Brig plug
1:05	320	300	95.37	43 Min	2.2	Start mixing Cement Displace Cement
1:45	1000	1000	4.25	2 Min	2.2	Test collar after Closing Circulate casing & Tubing Clean
			35	18 Min	1.9	Circulate casing & Tubing Clean Release Brig Plug & Bring out of Hole
						Cement did Circulate

RECEIVED
STATE CORPORATION COMMISSION

FEB 18 1986

DISP PRESS PSI BUMP PLUG TO PSI BLEEDBACK CONSERVATION DIVISION WICHITA, KANSAS

THANK YOU