

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas


Company - VIRGINIA DRILLING CO., INC.
Farm - Sack No. 1

SEC. 26 T. 13 R. 19W
NE NE NE

Total Depth. 3739'
Comm. 1-10-48 Comp. 1-22-48
Shot or Treated.
Contractor. Virginia Drilling Co., Inc.
Issued. 7-10-48

County. Ellis

KANSAS



Elevation. 2043 Ind

Production. Dry

Figures indicate Bottom of Formations.

surface soil	20
sand	60
shale	145
shale & shells	221
shale & shells	550
sand	650
shale, sand, shells	1050
shale & shells	1333
anhydrite	1378
shale & shells	1740
shale & salt	1830
shale & salt	1910
shale & shells	2200
shale & lime	2650
shale & shells	2750
shale & lime	2910
shale & shells	3035
shale & lime	3120
lime & shale	3250
10' corr. @ 3120'	
3120 = 3110	
lime	3290
lime & shale	3359
lime	3620
lime & conglomerate	3675
cherty conglo.	3711
arbuckle	3739
Total Depth	

Circulate:

3388 - 1 hour
3453 - 1 hour
3655 - 1 hour
3705 - 1 hr 9 min.
3734 - 1 hour

Tops:

Topeka	3068
Heebner sand	3312
Lansing K. C.	3375
Conglomerate	3649
Arbuckle	3703

Perforate 136 holes 3267-3512.

Filled w/wtr. Filled hole with
lead wool to shut off wtr.

Plugged back to 3427

Swabbed hole dry hole filled

1/2 wtr overnight Plugged back to 3294'

steel wool & calseal Swabbed hole

dry-filled w/wtr. Plug back to 3274.

Perforate 23 shots 3512-3504 wtr-no oil

" 22 " 3508-3500 WTR

" 21 " 3445-3553 "

" 24 " 3398-3406 "

" 46 " 3267-3283 "

" 160 " 3260-3290 NO results-little wtr, little oil

Plugged 3290-3200 calseal, rock & lead wool