

29-13-19w


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STERLING DRILLING COMPANY
Farm- Bemis 'A' No. 1

SEC. 29 T. 13 R. 19W
SW NW SW

Total Depth. 3880'
Comm. 7-15-57 Comp. 8-8-57
Shot or Treated.
Contractor. Sterling Drilling Company
Issued. 11-9-57

County Ellis KANSAS



Elevation. 2186'

Production. Dry

CASING:

8 5/8" 200' cem. w/140 sx
5 1/2" 3601' cem. w/75 sx

Figures indicate Bottom of Formations.

rock	200	
shale & shells	590	
shale	675	
sand	1200	
shale & shells	1505	
anhydrite	1545	
shale & shells	2365	
shale & lime	2495	
lime	2585	
shale & lime	3185	
lime	3280	
lime & shale	3365	
lime	3460	
lime & shale	3515	
lime	3555	
lime & shale	3600	
lime	3675	
lime & shale	3700	
lime	3725	
lime & shale	3840	
Conglomerate	3863	
Arbuckle	3880	RTD
Total Depth		

TOPS: Scout	
Heebner	3465
Toronto	3489
Lansing	3510
Base Kansas City	3764
Marmaton	3802
Cherty Conglomerate	3835
Arbuckle	3862

Perforated from 3537' to 3542' with 20 jet shots. Acidized with 55 Gal. 15% mud acid. Perforated from 3542' to 3548' with 24 jet shots. Acidized with 2000 gal. acid.