

31.13.190

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- ROCKET DRILLING COMPANY, INC.
Farm- Riedel No. 1

SEC. 31 T. 13 R. 19W
NE SE NE

Total Depth. 3923'
Comm. 12-17-57 Comp. 1-1-58
Shot or Treated.

County Ellis
KANSAS

Contractor. Bennett & Roberts Drilling Company
Issued. 3-1-58



CASING:

3 5/8" 248' cem w/150 sx
5 1/2" 3920' cem w/100 sx

Elevation. 2267'

Production. 25 BOPD

Figures indicate Bottom of Formations.

chalk rock	30
shale & shells	230
shale	420
shale & clay w/sand streaks	775
shale	930
red bed	1050
sand	1240
shale	1255
shale, shells, red bed	1555
Anhydrite	1607
shale & shells	1850
shale & lime	3486
chalky lime	3494
lime	3523
shale	3528
lime & shale	3538
lime	3825
lime & shale	3880
lime, conglomerate	3896
Conglomerate	3918
lime	3922-RTD
lime	3923-CTTD
Total Depth	

TOPS:

Anhydrite	2552
Topeka Lime	3269
Heebner Shale	3524
Toronto Lime	3545
Lansing-Kansas City	3565
Base Kansas City	3823
Cherty Conglomerate	3873
Arbuckle	3919